SE FLAVEL STREET EAST OF SE 152ND AVENUE SANITARY AND STORM IMPROVEMENTS HAWTHORNE MEADOWS SUBDIVISION - PHASE 1

GENERAL NOTES

- ERRORS AND OMISSIONS ARE THE RESPONSIBILITY OF THE "ENGINEER OF RECORD". IF ERRORS OR OMISSIONS ARE FOUND AFTER THE PERMIT HAS BEEN ISSUED, THE PERMITTEE OR ITS CONTRACTOR SHALL CONTACT THE ENGINEER OF RECORD (BEAU BRAMAN OF HHPR AT 503-221-1131) TO HAVE THE CORRECTIONS MADE. ALL CHANGES WILL REQUIRE THE APPROVAL OF THE CITY ENGINEER PRIOR TO THE WORK BEGINNING.
- 2. ALL CONSTRUCTION SHALL CONFORM TO 2010 CITY OF PORTLAND STANDARD CONSTRUCTION SPECIFICATIONS (SCS). CONTRACTOR AND/OR SUBCONTRACTOR SHALL HAVE A MINIMUM OF ONE SET OF APPROVED PLANS AND CITY OF PORTLAND STANDARD CONSTRUCTION SPECIFICATIONS ON THE JOB SITE AT ALL TIMES DURING
- ELEVATIONS ARE BASED ON CITY OF PORTLAND DATUM FROM BENCH MARK NO. 3505. LOCATED AT SE BELMORE STREET AND SE 152ND AVENUE.
- 4. ATTENTION EXCAVATORS: OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THESE RULES FROM THE CENTER BY CALLING [503.232.1987]. IF YOU HAVE ANY QUESTIONS ABOUT THE RULES, YOU MAY CONTACT THE CALL CENTER. YOU MUST NOTIFY THE CENTER AT LEAST 2 BUSINESS DAYS, BUT NOT MORE THAN 10 BUSINESS DAYS, BEFORE COMMENCING AN EXCAVATION. CALL [811 OR 1-800-332-2344].
- 5. CONTRACTOR SHALL MAINTAIN FLOWS IN THE EXISTING SYSTEM AT ALL TIMES.
- 6. ALL SEWER TRENCH LINES AND EXCAVATIONS SHALL BE PROPERLY SHORED AND BRACED TO PREVENT CAVING AS REQUIRED BY OREGON OCCUPATIONAL SAFETY AND HEALTH (OSHA) AND SECTION 00405.41(F) OF THE CITY OF PORTLAND STANDARD CONSTRUCTION SPECIFICATIONS.
- . EXCAVATED SEWER TRENCH SPOIL MATERIAL SHALL BE DISPOSED OF AT A PROPER LANDFILL, OR APPLICANT SHALL OBTAIN A FILL PERMIT FROM THE BUREAU OF DEVELOPMENT SERVICES BEFORE BEING DISPOSED OF ON-SITE. A COPY OF THE GRADING PERMIT AND PLAN SHALL BE PROVIDED TO THE BUREAU OF ENVIRONMENTAL SERVICES FOR CONSTRUCTION INSPECTION AT THE PRE-CONSTRUCTION MEETING. ANY WORK OUTSIDE THE PUBLIC RIGHT OF WAY, INCLUDING CUTS, FILLS, GRADING AND CLEARING MAY REQUIRE PERMITS FROM BUREAU OF DEVELOPMENT SERVICES.
- 8. UNANTICIPATED CONTAMINATION ENCOUNTERED DURING CONSTRUCTION IN CITY RIGHT OF WAY.
- A) THE APPLICANT IS RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH PROPER CHARACTERIZATION. IDENTIFICATION ANALYSIS. MANAGEMENT AND DISPOSAL OF CONTAMINATED MEDIA ENCOUNTERED WITHIN THE CITY RIGHT-OF-WAY OR ON CITY PROPERTY. THE APPLICANT IS ALSO RESPONSIBLE FOR ALL RESULTANT DELAYS.
- B) THE APPLICANT WILL PROVIDE THE CITY (ENGINEER AND INSPECTORS) WITH COPIES OF ALL DISPOSAL PERMITS FROM THE PERMITTED DISPOSAL FACILITY, ANALYTICAL RESULTS USED TO GAIN ACCEPTANCE OF THE CONTAMINATED MEDIA AND DISPOSAL RECEIPTS/DAILY WEIGH SLIPS. DAILY WEIGH SLIPS AMOUNTS SHALL BE CHECKED AGAINST INSPECTOR'S DAILY REPORTS. THE APPLICANT MUST USE AN OREGON DEPARTMENT OF ENVIRONMENTAL QUALITY - APPROVED DISPOSAL FACILITY FOR DISPOSAL OF THE CONTAMINATED MEDIA.
- 9. FOUNDATION STABILIZATION MAY BE NECESSARY AS PER CITY OF PORTLAND STANDARD CONSTRUCTION SPECIFICATIONS AND APPROVED BY BES.
- 10. MAINTAIN MINIMUM OF 36" COVER OVER ALL PIPE IN UNPAVED EASEMENT AREAS.
- 11. THE CONTRACTOR SHALL INSTALL MARKER BALLS ON ALL STORM AND SANITARY SEWER MAINLINE PIPE AND LATERALS. SEE SPECIFICATION SECTION 00446.
- 12. MARK ENDS OF ALL STUB OUTS AND LATERALS W/ CONTINUOUS PRESSURE TREATED 2" X 4" TOP 12" TO BE PAINTED WHITE AND STENCILED WITH BLACK 'ST' FOR STORM OR PAINTED GREEN AND STENCILED BLACK "SS" FOR SANITARY AND WITH PIPE SIZE, MATERIAL TYPE, AND PIPE DEPTH. BURY 2" X 4" TO I.E. OF STUB OR
- 13. CITY OF PORTLAND MAINTENANCE OF HOUSE BRANCHES END AT THE CURB LINE IN RIGHTS-OF-WAY AND AT THE END OF THE TEE IN EASEMENTS.
- 14. INSTALL LATERAL CURB MARKERS ON ALL NEW LATERALS PER SPECIFICATION 00446.11.
- 15. BUREAU OF DEVELOPMENT SERVICES (BDS) PLUMBING DIVISION APPROVALS AND PERMITS ARE REQUIRED FOR PRIVATELY MAINTAINED SEWER, INLETS, INLET LEADS & SERVICE LATERALS CONSTRUCTED OUTSIDE OF PUBLIC RIGHT OF WAY OR SEWER EASEMENT. ALL WORK APPROVED UNDER PLUMBING PERMITS SHALL BE PRIVATELY OWNED AND MAINTAINED.
- 16. STREET RESTORATION SHALL BE PER THE REQUIREMENTS OF THE PBOT STREET OPENING PERMIT.

PIPE TESTING REQUIREMENTS

- 17. ALL STORM AND SANITARY SEWERS WILL BE AIR TESTED AND SHALL BE SUBJECT TO OTHER TESTING REQUIREMENTS AS OUTLINED IN THE CITY OF PORTLAND STANDARD CONSTRUCTION SPECIFICATIONS.
- 18. SEWER SHALL BE VIDEO INSPECTED (TV'D) AT THE SOLE EXPENSE OF THE APPLICANT/CONTRACTOR.
- 19. MANDREL TESTING IS REQUIRED ON ALL HDPE AND PVC PIPE. A 30-DAY WAITING PERIOD IS REQUIRED ON ALL MANDREL TESTING.

PRECONSTRUCTION REQUIREMENTS

- 20. A TEMPORARY TRAFFIC CONTROL PLAN (TTCP) IS REQUIRED BEFORE ANY WORK CAN COMMENCE WITHIN THE PUBLIC RIGHT OF WAY. THE TTCP IS PART OF THE TEMPORARY USE OF THE RIGHT OF WAY PERMIT. THE APPLICATION CAN BE FOUND AT: HTTP: //WWW.PORTLANDOREGON.GOV/TRANSPORTATION/ARTICLE/174124
- 21. A COPY (EITHER ELECTRONIC OR PAPER) OF THE APPROVED TTCP SHALL BE PROVIDED TO THE INSPECTOR BEFORE ANY STREET OR SIDEWALK CLOSURES. CONTACT BEN BALDWIN AT TRI-MET 14 DAYS PRIOR TO STARTING CONSTRUCTION AT 503-962-2140.
- 22. SITE EROSION CONTROL PLANS TO BE APPROVED AND CONTROLS IN PLACE PRIOR TO GRADING AND WORKING IN THE RIGHT OF WAY. APPLICANT/CONTRACTOR TO PUT UP ALL REQUIRED EROSION CONTROL SIGNAGE PRIOR TO GROUND DISTURBANCE. A CD WITH ALL REQUIRED EROSION CONTROL SIGNS WILL BE PROVIDED AT PRE-CONSTRUCTION MEETING.
- 23. LOCATIONS OF EXISTING STRUCTURES AND UTILITIES ARE FOR INFORMATION PURPOSES ONLY. APPLICANT/CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE LOCATION AND DEPTH (ELEVATION) OF EXISTING UTILITIES AND OTHER FIELD CONDITIONS PRIOR TO CONSTRUCTION.

24. PRECONSTRUCTION MEETING REQUIRED. APPLICANT/CONTRACTOR TO CONTACT BES A MINIMUM OF 4 BUSINESS DAYS PRIOR TO COMMENCEMENT OF CONSTRUCTION TO SCHEDULE MEETING. FOLLOW INSTRUCTIONS OF "PERMIT ISSUANCE" EMAIL TO SCHEDULE A MEETING.

ADDITIONAL NOTES

- 25. ALL COST OF SANITARY SEWER CONSTRUCTION BORNE BY ALL LOTS IN HAWTHORNE MEADOWS PHASE 1.
- 26. PUBLIC STREET IMPROVEMENTS, INLETS, AND INLET LEADS TO BE CONSTRUCTED UNDER PORTLAND OFFICE OF TRANSPORTATION PERMIT JOB NO. TH0269.

STORMWATER NARRATIVE

CATEGORY 3 STORMWATER MANAGEMENT IS ACHIEVED BY PROVIDING TREATMENT AND FLOW CONTROL THROUGH FLOW THRU FACILITIES ON BOTH PRIVATE AND PUBLIC PROPERTY BEFORE BEING PIPED TO THE EXISTING STORMWATER ONLY SYSTEM IN SE 152ND AVENUE, THEREFORE MEETING THE 2014 PORTLAND STORMWATER MANAGEMENT MANUAL REQUIREMENTS.

PUBLIC:

STORMWATER RUNOFF MANAGEMENT FOR THE PUBLIC ROADWAY WILL BE PROVIDED BY STREET SIDE FLOW THRU STORMWATER FACILITIES. THE FLOW THRU STORMWATER PLANTERS WILL PROVIDE BOTH FLOW CONTROL AND WATER QUALITY TREATMENT. THE PRIVATE STORMWATER RUNOFF WILL BE MANAGED ON THE PROPERTIES BEFORE BEING PIPED TO THE PUBLIC STORMWATER SYSTEM IN THE ROADWAY. IN BOTH THE PUBLIC AND PRIVATE CASES, AFTER INFILTRATING WITHIN THE STORMWATER PLANTER, STORMWATER WILL BE PIPED TO THE EXISTING STORMWATER ONLY SYSTEM IN SE 152ND AVENUE.

FOR THE PUBLIC IMPERVIOUS AREA, STORMWATER RUNOFF FLOWS FROM THE STREET CENTERLINE TO THE GUTTERS ON EITHER EDGE OF THE STREET AND THEN INTO STORMWATER FLOW THRU FACILITIES. FOCUSED AT THE LOW POINTS OF THE ROAD. THE STORMWATER FLOW THRU FACILITIES PROVIDE BOTH STORMWATER TREATMENT AND FLOW CONTROL. THERE IS PERFORATED PIPE RUNNING THE LENGTH OF ALL THE STORMWATER FACILITIES. AFTER INFILTRATING THROUGH THE GROWING MEDIUM AND DRAIN ROCK, THE STORMWATER RUNOFF WILL ENTER THE PERFORATED PIPE AND BE HARD PIPED INTO THE PUBLIC STORMWATER CONVEYANCE SYSTEM WITHIN THE STREET. THE STORMWATER FACILITIES ARE ARRANGED SUCH THAT OVERFLOWING WATER WILL DRAIN INTO ADJACENT FACILITIES TO MAXIMIZE STORMWATER TREATMENT AND FLOW CONTROL. AT BOTH ENDS OF THE PROPOSED ROADWAY ARE CATCH BASINS DESIGNED TO CATCH ANY RUNOFF THAT MIGHT OVERFLOW THE FACILITIES DURING THE LARGE STORM EVENTS. THE CATCH BASINS ARE PIPED INTO THE STORMWATER CONVEYANCE SYSTEM. THE NEW STORMWATER SYSTEM CONNECTS TO THE EXISTING SYSTEM BY TYING INTO AN EXISTING STORM MANHOLE IN 152ND AVENUE. TABLE 1 SHOWS A SUMMARY OF THE SIZES OF THE PUBLIC BASINS AND FACILITIES. TABLE 2 SHOWS THE PRE-CONSTRUCTION AND POST-CONSTRUCTION FACILITIES FOR THE PUBLIC BASINS.

PRIVATE:

RUNOFF FROM THE HOUSE ROOFS AND DRIVEWAYS (PRIVATE BASINS) WILL BE PIPED INTO FACILITIES ON PRIVATE PROPERTY TO PROVIDE THE REQUIRED TREATMENT AND FLOW CONTROL. THE RUNOFF WILL THEN BE PIPED TO THE PROPOSED CONVEYANCE SYSTEM. THE PRIVATE STORMWATER FACILITIES WERE SIZED BASED ON THE AVERAGE LOT SIZE AND THE AVERAGE IMPERVIOUS AREA USING THE SIMPLIFIED METHOD SIZING FACTOR OF 0.09.

SHEET INDEX

EC 1

COVER SHEET

BES DETAILS

BES DETAILS

BES DETAILS

BES DETAILS

EROSION CONTROL PLAN

EROSION CONTROL DETAILS

EXISTING CONDITIONS

SITE PLAN & DRAINAGE BASIN MAP

SANITARY SEWER PLAN & PROFILE

STORM SEWER PLAN & PROFILE

PUBLIC IMPERVIOUS AREA MANAGED: 24,945 SF

PUBLIC STORMWATER FACILITIES: 2,725 SF

PRIVATE IMPERVIOUS AREA MANAGED: 35,840 SF

PRIVATE STORMWATER FACILITIES: 3.848 SF

NOTICE TO EXCAVATORS:

ATTENTION: OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THE RULES BY CALLING THE CENTER. (NOTE: THE TELEPHONE NUMBER FOR

THE OREGON UTILITY NOTIFICATION CENTER IS 503-232-1987).

POTENTIAL UNDERGROUND FACILITY OWNERS

Dig Safely.

Call the Oregon One-Call Center DIAL 811 or 1-800-332-2344

EMERGENCY TELEPHONE NUMBERS


NW NATURAL GAS M-F 7am-6pm


503-226-4211 Ext.4313 AFTER HOURS 503-226-4211 PGE 503-464-7777 CENTURYLINK 1-800-573-1311


CITY BUREAU OF MAINTENANCE 503-823-1700 CITY WATER 503-823-4874 VERIZON 1-800-483-1000

PROPOSED

LEGEND







VICINITY MAP

SK Barbara Welch Ac	Clatsop Butte City Park	
0 4		斎
Park 7A	-PLEASANT VALLEY	<u>ē</u>
	W St. Syllest -	Kellev Creek
	SE Oggen Di Se Station SE Henderson Way	
	SE Henderson Way	
	\$4 ₀₀	ří
	70 Pb	62nc
	PROJECT LOCATION	162nd Ave
18 CT	.	

Harper

HHPR Houf Peterson Righellis Inc.

EXPIRES: 12/31/2017

SE FLAVEL STREET E/O SE 152ND **AVENUE SEWER IMPROVEMENTS**

HAWTHORNE MEADOWS SUBDIVISION - PHASE 1 15 - 195679 LU

HEET NO. 1 OF 9

BES JOB NO.

EP204

Agu BJB CONSTRUCTED BY ROJECT COMPLETED . GHD MAP CORRECTED BY HECKED BY CHECKED BY. **BMH** DESCRIPTION NO. DATE FINAL MAP DATA REVISIONS


APPROVAL:


BUREAU OF **ENVIRONMENTAL SERVICES**


NICK FISH COMMISSIONER WILLIAM F. RYAN, P.E. CHIEF ENGINEER


LANDSCAPE ARCHITECTS . SURVEYORS 205 SE Spokane Street, Suite 200, Portland, OR 97202 phone: 503.221.1131 www.hhpr.com fax: 503.221.1171

COVER SHEET











CONSTRUCTION NOTES

- 1) CONSTRUCT 48" MANHOLE. SEE STD. DRGS. P-150 & P-151. SEE PIPE ANGLE DETAIL THIS SHEET.
- (2) CONSTRUCT 6" STORM LATERAL. SEE STD. DRG. P-262.
 - 3 CONNECT TO EXISTING STORM MANHOLE. ADJUST RIM TO FINISH GRADE. STORM STA: 0+00.00 STREET CL STA: 00+02.91 RE-CHANNEL BOTTOM
- 4 CONTRACTOR TO POTHOLE EXISTING WATER AND GAS ON SE 152ND AVENUE PRIOR TO CONSTRUCTION TO CONFIRM CLEARANCE AND MEET SEPERATION REQUIREMENTS.



PIPE ANGLE DETAIL - STM MH 1







<u>PIPE ANGLE DETÄIL — STM MH 3</u>

STORM FACILITY LATERAL TABLE										
SERVICE LATERALS SHALL BE 6" HDPE, ASTM D3350 PIPE. INSTALL AT 2% MINIMUM SLOPE. FLEXIBLE PIPE BEDDING PER 00405.12 & 00405.45 AND BACKFILL PER 00405.14 & 00405.46.										
LOT # STATION IE OF MAIN IE OF LAT @ IE @ PIPE LENGTH SLO MAIN CLEANOUT PIPE LENGTH N										
2	1+00.15	445.26	445.64	450.24	20.25'	0.2273				
3	1+73.15	448.45	448.82	457.54	20.25'	0.4306				
7	4+99.15	454.48	454.86	457.80	20.25'	0.1454				
10	4+48.97	453.98	454.35	460.38	16.75'	0.3597				
11	3+88.97	453.38	453.75	464.62	16.75'	0.6487				
14	1+85.97	449.00	449.38	458.82	16.75'	0.5636				
15	1+18.47	446.06	446.44	452.07	16.75'	0.3363				
16	0+60.29	443.53	443.90	446.51	16.75'	0.1558				

10	0+60.29	443.33	445.90	440.31	16.75	0.1556
	STO	ORM DRAII	N SERVICE	LATERAL	. TABLE	
					AT 2% MINIMUM SL R 00405.14 & 004	
LOT #	LOT # STATION IE OF MAIN IE OF LAT @ IE @ R.O.W. PIPE LENGTH SLO MAIN IE @ R.O.W. WITHIN R.O.W. R.					
1	0+78.65	444.33	444.70	449.00	31'	0.1387
2	1+47.12	447.31	447.69	455.50	31'	0.2521
3	2+06.62	449.91	450.28	462.00	31'	0.3781
4	2+73.69	452.23	452.60	466.00	31'	0.4322
5	3+24.09	452.73	453.11	466.00	31'	0.4159
6	3+93.93	453.43	453.80	465.00	31'	0.3612
7	4+59.09	454.08	454.46	460.00	31'	0.1789
8	5+12.74	454.62	454.99	457.50	31'	0.0809
9	5+04.17	454.53	454.91	457.00	27'	0.0775
10	4+70.47	454.19	454.57	459.00	27'	0.1641
11	4+10.47	453.59	453.97	463.00	27'	0.3345
12	3+32.47	452.81	453.19	466.00	27'	0.4745
13	2+56.44	452.05	452.43	465.00	27'	0.4656
14	2+15.97	450.31	450.69	462.00	27'	0.4190
15	1+56.47	447.72	448.09	456.00	27'	0.2928
16	0+94.97	445.04	445.41	450.00	27'	0.1699



DE.S					DESIGNED BY		D.E. APPROVAL
n				CONSTRUCTED BY	BJB	1	mac
4				PROJECT COMPLETED	CAD BY	!	CONST. APPROVAL
1					GHD	1	-#
-				MAP CORRECTED BY	CHECKED BY	1	
- - - - - - - - - - - - - - - - - - -				CHECKED BY	ВМН	1	
	 DATE	DESCRIPTION	APPD.				
릴		REVISIONS		FINAL MAP DATA	,		



APPROVAL:

BUREAU OF ENVIRONMENTAL SERVICES

NICK FISH WILLIAM F. RYAN, P.E.

COMMISSIONER LANDSCAPE ARCHITECTS + SURVEYORS CHIEF ENGINEER



205 SE Spokane Street, Suite 200, Portland, OR 97202

phone: 503.221.1131 www.hhpr.com fax: 503.221.1171

EXPIRES: 12/31/2017

SE FLAVEL STREET E/O SE 152ND **AVENUE SEWER IMPROVEMENTS**


HAWTHORNE MEADOWS SUBDIVISION - PHASE 1 15 - 195679 LU


4 OF 9

EP204


SHEET NO.

STORM SEWER PLAN AND PROFILE






- 1) CONSTRUCT 48" MANHOLE. SEE STD. DRGS. P-150 & P-151. SEE PIPE ANGLE DETAIL THIS SHEET.
- (2) CONSTRUCT 6" SANITARY LATERAL. SEE STD. DRG. P-262.
- 3 CONNECT TO EXISTING SANITARY MANHOLE. ADJUST RIM TO FINISH GRADE. SANITARY STA: 0+00.00 STREET CL STA: 00+01.01
 - SEE ODOT STD DWG RD339 FOR CONNECTION DETAIL. RE-CHANNEL BOTTOM
- (4) CONTRACTOR TO POTHOLE EXISTING WATER AND GAS ON SE 152ND AVENUE PRIOR TO CONSTRUCTION TO CONFIRM CLEARANCE AND MEET SEPERATION REQUIREMENTS.




PIPÉ ANGLE DETAIL - SAN MH 1

PIPE ANGLE DETAIL - SAN MH 2




PIPE ANGLE DETAIL - SAN MH 3



SERVICE LATERALS SHALL BE HDPE PIPE. FLEXIBLE PIPE BEDDING PER 00405.12 & 00405.45 AND BACKFILL PER 00405.14 & 00405.46.									
LOT # STATION IE OF MAIN IE OF LAT @ IE @ R.O.W. PIPE LENGT									
1	1+03.84	442.46	442.54	449.00	23'	0.280			
2	1+68.84	445.44	445.53	455.50	23'	0.433			
3	2+35.82	448.52	448.60	462.00	23'	0.5820			
4	2+98.86	450.64	450.72	466.00	23'	0.664.			
5	3+49.28	451.14	451.23	466.00	23'	0.642			
6	4+19.12	451.84	451.93	465.00	23'	0.568.			
7	4+84.28	452.49	452.58	460.00	23'	0.322			
8	5+34.44	453.00	453.08	457.50	23'	0.192			
9	5+23.66	452.89	452.97	453.67	35'	0.020			
10	4+99.67	452.65	452.73	453.43	35'	0.020			
11	4+39.66	452.05	452.13	452.83	35'	0.020			
12	3+57.66	451.23	451.31	452.01	35'	0.0200			
13	2+85.63	450.51	450.59	451.29	35'	0.0200			
14	2+45.16	448.95	449.03	449.73	35'	0.0200			
15	1+85.75	446.22	446.30	447.00	35'	0.020			
16	1+24.17	443.39	443.48	444.18	35'	0.0200			

NOTE: LOTS 9, 10, & 16 WILL NEED PRIVATE GRINDER PUMPS FOR DAYLIGHT FLOOR CONSTRUCTION



BES		,				DESIGNED BY		D.E. APPROVAL
an I					CONSTRUCTED BY	BJB		1 19TW
5					PROJECT COMPLETED	CAD BY	ŀ	CONST. APPROVAL
-1	· =		,			GHD	Ì	-#+
0		· · · .			MAP CORRECTED BY	CHECKED BY	!	
JTS					CHECKED BY	ВМН	l	
щ	NO.	DATE	DESCRIPTION	APPD.				
글			RFVISIONS		FINAL MAP DATA	1		



APPROVAL:


BUREAU OF ENVIRONMENTAL SERVICES

COMMISSIONER

CHIEF ENGINEER

Harper HHPR Houf Peterson Righellis Inc.

ENGINEERS * PLANNERS LANDSCAPE ARCHITECTS * SURVEYORS 205 SE Spokane Street, Suite 200, Portland, OR 97202 phone: 503.221.1131 www.hhpr.com fax: 503.221.1171




SE FLAVEL STREET E/O SE 152ND **AVENUE SEWER IMPROVEMENTS**


HAWTHORNE MEADOWS SUBDIVISION - PHASE 1 15 - 195679 LU


SANITARY SEWER PLAN AND PROFILE


EP204 SHEET NO. 5 OF 9


BES JOB NO.











FINAL MAP DATA

REVISIONS



APPROVAL:



ENVIRONMENTAL SERVICES

COMMISSIONER

WILLIAM F. RYAN, P.E. CHIEF ENGINEER



phone: 503.221.1131 www.hhpr.com fax: 503.221.1171

ENGINEERS * PLANNERS LANDSCAPE ARCHITECTS * SURVEYORS 205 SE Spokane Street, Suite 200, Portland, OR 97202

EXPIRES: 12/31/2017

SE FLAVEL STREET E/O SE 152ND **AVENUE SEWER IMPROVEMENTS HAWTHORNE MEADOWS SUBDIVISION - PHASE 1**

BES DETAILS

15 - 195679 LU


SHEET NO.


BES JOB NO.


EP204


6 OF 9

BUREAU OF










. Ш		1		1		
Ш					CONSTRUCTED BY	BJB
7					PROJECT COMPLETED	CAD BY
. 1						GHD
0			`		MAP CORRECTED BY	CHECKED BY
JTS					CHECKED BY	ВМН
	NO.	DATE	DESCRIPTION	APPD.		

REVISIONS

FINAL MAP DATA




APPROVAL:



BUREAU OF ENVIRONMENTAL SERVICES

COMMISSIONER

CHIEF ENGINEER



ENGINEERS * PLANNERS LANDSCAPE ARCHITECTS . SURVEYORS 205 SE Spokane Street, Suite 200, Portland, OR 97202 phone: 503.221.1131 www.hhpr.com fax: 503.221.1171



SE FLAVEL STREET E/O SE 152ND **AVENUE SEWER IMPROVEMENTS**

HAWTHORNE MEADOWS SUBDIVISION - PHASE 1

15 - 195679 LU


BES DETAILS


SHEET NO.


BES JOB NO.


EP204


7 OF 9














APPROVAL:



BUREAU OF ENVIRONMENTAL SERVICES

CHIEF ENGINEER

FISH COMMISSIONER



LANDSCAPE ARCHITECTS . SURVEYORS

205 SE Spokane Street, Suite 200, Portland, OR 97202

phone: 503.221.1131 www.hhpr.com fax: 503.221.1171

OREGON

OREGON

OREGON

OREAU J. BRAMAN

EXPIRES: 12/31/2017


SE FLAVEL STREET E/O SE 152ND
AVENUE SEWER IMPROVEMENTS
HAWTHORNE MEADOWS SUBDIVISION - PHASE 1


IE MEADOWS SUBDIVISION - PH/ 15 - 195679 LU

BES DETAILS

EP204 SHEET NO. 8 OF 9

BES JOB NO.





Bonw


APPROVAL:

HIEF ENGINEER J REG. PROF. ENGR. 16301PE

BUREAU OF ENVIRONMENTAL SERVICES

NICK FISH

COMMISSIONER
CHIEF ENGINEER



ENGINEERS * PLANNERS
LANDSCAPE ARCHITECTS * SURVEYORS

205 SE Spokane Street, Suite 200, Portland, OR 97202
phone: 503.221.1131 www.hhpr.com fax: 503.221.1171



SE FLAVEL STREET E/O SE 152ND
AVENUE SEWER IMPROVEMENTS
HAWTHORNE MEADOWS SUBDIVISION - PHASE

HAWTHORNE MEADOWS SUBDIVISION - PHASE 1 15 - 195679 LU

BES DETAILS


9 OF 9

SHEET NO.

BES JOB NO.

EP204

S.DWG Layout1 9/5/2017 4:05:02 PM - NATH



GENERAL NOTES FOR EROSION SEDIMENT AND POLLUTION CONTROL

- 1. APPROVAL OF THIS EROSION SEDIMENT AND POLLUTION CONTROL PLAN (ESPCP) DOES NOT CONSTITUTE AN APPROVAL OF PERMANENT ROAD OR DRAINAGE DESIGN (E.G., SIZE AND LOCATION OF ROADS, PIPES, RESTRICTORS, CHANNELS, RETENTION FACILITIES, UTILITIES, ETC.)
- 2. THE IMPLEMENTATION OF THIS ESPCP AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT AND UPGRADING OF THESE ESPCP FACILITIES IS THE RESPONSIBILITY OF THE APPLICANT/CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED, VEGETATION/LANDSCAPING IS ESTABLISHED.
- THE BOUNDARIES OF THE CLEARING LIMITS SHOWN ON THIS PLAN SHALL BE CLEARLY FLAGGED IN THE FIELD PRIOR TO CONSTRUCTION. DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE FLAGGED CLEARING LIMITS SHALL BE PERMITTED. THE FLAGGING SHALL BE MAINTAINED BY THE APPLICANT/CONTRACTOR FOR THE DURATION OF CONSTRUCTION.
- 4. THE ESPCP FACILITIES SHOWN ON THIS PLAN MUST BE CONSTRUCTED IN CONJUNCTION WITH ALL CLEARING AND GRADING ACTIVITIES, AND IN SUCH A MANNER AS TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT ENTER THE DRAINAGE SYSTEM ROADWAYS OR VIOLATE APPLICABLE WATER STANDARDS.
- 5. THE ESPCP FACILITIES SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE ESPCP FACILITIES SHALL BE UPGRADED AS NEEDED FOR UNEXPECTED STORM EVENTS, AND TO ENSURE THAT SEDIMENT AND SEDIMENT-LADEN WATER DOES NOT LEAVE THE SITE.
- 6. THE ESPCP FACILITIES SHALL BE INSPECTED DAILY BY THE APPLICANT/CONTRACTOR AND MAINTAINED AS NECESSARY TO ENSURE THEIR CONTINUED FUNCTIONING.
- 7. THE ESPCP FACILITIES ON INACTIVE SITES SHALL BE INSPECTED AND MAINTAINED A MINIMUM OF ONCE A WEEK OR WITHIN THE 24 HOURS FOLLOWING A STORM EVENT.
- 8. STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES MAY BE REQUIRED TO ENSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
- APPLICANT/CONTRACTOR TO PUT UP ALL REQUIRED EROSION CONTROL SIGNAGE PRIOR TO GROUND DISTURBANCE. A CD WITH ALL REQUIRED EROSION CONTROL SIGNS WILL BE PROVIDED AT THE PRE-CONSTRUCTION MEETING.

SEDIMENTATION FENCE NOTES


- 10. THE FILTER FABRIC FENCE SHALL BE INSTALLED TO FOLLOW THE CONTOURS WHERE FEASIBLE. THE FENCE POSTS SHALL BE SPACED A MAXIMUM OF 6' APART AND DRIVEN SECURELY INTO THE GROUND A MINIMUM OF 24".
- 11. THE FILTER FABRIC SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID USE OF JOINTS. WHEN JOINTS ARE NECESSARY, FILTER CLOTH SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST, WITH A MINIMUM OF 6" OVERLAP AND BOTH ENDS SECURELY FASTENED TO THE POST, OR OVERLAP 2"X2" POSTS AND ATTACH AS SHOWN ON DETAIL SHEET 4.3-A OF THE EROSION CONTROL MANUAL.
- 12. THE FILTER FABRIC SHALL HAVE A MINIMUM VERTICAL BURIAL OF 6". ALL EXCAVATED MATERIAL FROM FILTER FABRIC INSTALLATION SHALL BE BACKFILLED AND COMPACTED ALONG THE ENTIRE DISTURBED
- 13. THE STANDARD OR HEAVY-DUTY FILTER FABRIC FENCES SHALL HAVE MANUFACTURED STITCHED LOOPS FOR 2"X2" POST INSTALLATION. STITCHED LOOPS SHALL BE INSTALLED ON THE UPHILL SIDE OF THE SLOPED AREA.
- 14. FILTER FABRIC FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY PROTECTED AND STABILIZED.
- 15. FILTER FABRIC FENCES SHALL BE INSPECTED BY APPLICANT/CONTRACTOR IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.

CONSTRUCTION NOTES

- (1) INLET SEDIMENT CONTROL DEVICE (TYP).
- (2) INSTALL GRAVEL CONSTRUCTION ENTRANCE.
- (3) INSTALL TREE PROTECTION FENCE.
- (4) INSTALL SEDIMENT FENCE AT LIMITS OF GRADING & CONSTRUCTION.
- 5 INSTALL CONSTRUCTION FENCE AT PROPERTY LINE LIMITS OF GRADING AND CONSTRUCTION.
- (6) INSTALL CONCRETE TRUCK WASHOUT BASIN.

EMERGENCY CONTACT

COMPANY / AGENCY: Redacted CONTACT: Redacted PHONE: Redacted E-MAIL: Redacted



	<i>j</i>	DESIGNED BY	1	D.E. APPROVAL
	CONSTRUCTED BY	BJB	1	Bon
		CAD BY	\neg	CONST ADDROVAL

NO. DATE

PROJECT COMPLETED GHD HECKED BY **BMH** HECKED B DESCRIPTION **REVISIONS** FINAL MAP DATA



BUREAU OF ENVIRONMENTAL SERVICES

COMMISSIONER


CHIEF ENGINEER

NICK FISH

WILLIAM F. RYAN, P.E.

HHPR Houf Peterson Righellis Inc.

ENGINEERS * PLANNERS LANDSCAPE ARCHITECTS + SURVEYORS 205 SE Spokane Street, Suite 200, Portland, OR 97202 phone: 503.221.1131 www.hhpr.com fax: 503.221.1171




SE FLAVEL STREET E/O SE 152ND **AVENUE SEWER IMPROVEMENTS HAWTHORNE MEADOWS SUBDIVISION - PHASE 1**


15 - 195679 LU

EROSION CONTROL PLAN


BES JOB NO. EP204 HEET NO. EC 1



50' MIN. (20' FOR 1 & 2 FAMILY HOMES) ─ WHEEL WASH AREA (IF REQ'D) -SILT FENCE (SEE SILT FENCE DETAIL) DRAINAGE RAMP - FULL WIDTH RAMP — FULL WIDTH OF ENTRY MINIMUM WIDTH **GRAVEL CONSTRUCTION ENTRANCE** EROSION CONTROL MANUAL GRAVEL CONSTRUCTION ENTRANCE Detail Drawing 4.2-A FILE DRAFT:INSPECTORS GRAPHICS DRAWING DR 3.3.1 PLOT 1:1



- 1. TREE PROTECTION SHALL BE A MINIMUM OF 6'-0" ORANGE PLASTIC MESH AND BE SECURED TO THE GROUND WITH 8'-0" METAL POSTS OR 6'-0" HIGH CHAIN LINK FENCE SUPPORTED BY
- TREE PROTECTION FENCING SHALL BE ERECTED OUTSIDE OF THE DRIP LINE ZONE PRIOR TO ANY CLEARING, GRADING OR OTHER CONSTRUCTION ACTIVITY. CONTRACTOR TO MAINTAIN TREE PROTECTION FENCING IN PLACE DURING CONSTRUCTION.




- 1. COLLECT AND RETAIN ALL THE CONCRETE WASHOUT WATER AND SOLIDS IN A LEAK PROOF BASIN.
- 2. INSPECT FREQUENTLY. DO NOT OVERFILL BASIN.

STORM OR SANITARY SYSTEM.


- 3. RECYCLE MATERIALS. A. WASHWATER RECYCLING: WASHWATER SHOULD BE PASSED THROUGH A FILTER AND TREATMENT SYSTEM TO REMOVE SOLIDS AND REDUCE PH. WASHWATER MAY BE REUSED FOR CONCRETE WASHOUT WATER. DISPOSAL OF WASHWATER SHALL BE AT AN APPROVED DISPOSAL FACILITY. DO NOT DRAIN TO
 - B. SOLIDS RECYCLING: COURSE AGGREGATE MATERIALS THAT ARE SEPARATED FROM WASHWATER MAY BE RETURNED TO READY MIX PLANT. COORDINATE WITH READY MIX PLANT PRIOR TO CONSTRUCTION. C. HARDENED CONCRETE RECYCLING: ALLOW CONCRETE WASHOUT TO HARDEN IN BASIN. THE HARDENED CONCRETE MAY BE DELIVERED TO RECYCLING PLANTS.

CONCRETE TRUCK WASHOUT BASIN



ORANGE CONSTRUCTION FENCE

				· · · · · · · · · · · · · · · · · · ·	
					DESIGNED BY
	t .			CONSTRUCTED BY	BJB
				PROJECT COMPLETED	CAD BY
					GHD
				MAP CORRECTED BY	CHECKED BY
				CHECKED BY	ВМН
NO.	DATE	DESCRIPTION	APPD.		
· ·		REVISIONS		FINAL MAP DATA	








BUREAU OF ENVIRONMENTAL SERVICES

NICK FISH COMMISSIONER WILLIAM F. RYAN, P.E. CHIEF ENGINEER



ENGINEERS * PLANNERS LANDSCAPE ARCHITECTS + SURVEYORS 205 SE Spokane Street, Suite 200, Portland, OR 97202 phone: 503.221.1131 www.hhpr.com fax: 503.221.1171



SE FLAVEL STREET E/O SE 152ND **AVENUE SEWER IMPROVEMENTS HAWTHORNE MEADOWS SUBDIVISION - PHASE 1**

15 - 195679 LU

EROSION CONTROL DETAILS

EP204 HEET NO. EC 2

BES JOB NO.