


01 	Vision: Improving Corridor Coordination	05
	Introduction and goals	
02 	The Columbia and Lombard Corridors Today	09
	Summary of existing conditions	
03 	Plan Process	31
	Plan timeline and summary of public engagement	
04 	Project Recommendations	37
	Corridor and other network recommendations	
05 	Additional Recommendations	63
	General and policy recommendations	
06 	Implementation and Next Steps	75
	Identifying top projects and a strategy for implementation	
	Appendices	
	• A) Existing Conditions and Policy Review	
	• B) Safety Analysis	
	• C) Mobility and Access Needs Analysis	
	• D) Railroad Crossing Analysis	
	• E) Recommended Transportation System Plan Changes	
	• F) Project List	

Columbia Lombard Mobility Plan

Introduction and Goals

The Columbia Lombard Mobility Corridor Plan originated out of a collective recognition that these corridors are not functioning as they should. Some of the well-known issues include unsafe and unpredictable road conditions, limited access to jobs and services, constraints to efficient freight movement, unclear priorities and a lack of investment in maintenance.

The goal of the Columbia Lombard Mobility Corridor Plan is to identify and prioritize projects and strategies that will improve safety, connectivity and access for people walking and biking, and improve the reliability of freight movement along and across these corridors.






Columbia Lombard Mobility Plan – Existing Conditions

CHAPTER 02

THE COLUMBIA AND LOMBARD CORRIDORS TODAY

Context, issues, and existing conditions on the Columbia and Lombard Corridors

CORRIDOR CONCEPTUAL MAP



CHAPTER 02

COLUMBIA BOULEVARD – TOTAL, FATAL, SERIOUS INJURY, PEDESTRIAN AND BICYCLIST CRASHES BY LOCATION

Lombard Project Corridor

Crash Injury Severity

- Fatal (K) Crash
- Serious Injury (A) Crash
- Evident (B) or Possible (C) Crash

Density - All Crashes

- Low
- Medium
- High

City of Portland Parks

School Sites

Inset Map Legend

- Lombard Project Corridor
- Crash Injury Severity
- Fatal (K) Crash, Pedestrian
- Serious Injury (A) Crash, Pedestrian
- Evident (B) or Possible (C) Injury Crash, Bicyclist

Map Labels

- N Chataqua Ave
- N Perlin Ave
- N Greeley Ave
- N Denver Ave
- N Interstate Ave
- N Vancouver Ave
- NE 33rd Dr
- NE 42nd Ave
- NE 60th Ave
- NE 72nd Ave
- NE 84th Ave
- NE Cully Blvd
- NE Killingsworth St
- NE King Jr Blvd
- NE 15th St
- NE 20th St
- NE 25th St
- NE 30th St
- NE 35th St
- NE 40th St
- NE 45th St
- NE 50th St
- NE 55th St
- NE 60th St
- NE 65th St
- NE 70th St
- NE 75th St
- NE 80th St
- NE 85th St
- NE 90th St
- NE 95th St
- NE 100th St
- NE 105th St
- NE 110th St
- NE 115th St
- NE 120th St
- NE 125th St
- NE 130th St
- NE 135th St
- NE 140th St
- NE 145th St
- NE 150th St
- NE 155th St
- NE 160th St
- NE 165th St
- NE 170th St
- NE 175th St
- NE 180th St
- NE 185th St
- NE 190th St
- NE 195th St
- NE 200th St
- NE 205th St
- NE 210th St
- NE 215th St
- NE 220th St
- NE 225th St
- NE 230th St
- NE 235th St
- NE 240th St
- NE 245th St
- NE 250th St
- NE 255th St
- NE 260th St
- NE 265th St
- NE 270th St
- NE 275th St
- NE 280th St
- NE 285th St
- NE 290th St
- NE 295th St
- NE 300th St
- NE 305th St
- NE 310th St
- NE 315th St
- NE 320th St
- NE 325th St
- NE 330th St
- NE 335th St
- NE 340th St
- NE 345th St
- NE 350th St
- NE 355th St
- NE 360th St
- NE 365th St
- NE 370th St
- NE 375th St
- NE 380th St
- NE 385th St
- NE 390th St
- NE 395th St
- NE 400th St
- NE 405th St
- NE 410th St
- NE 415th St
- NE 420th St
- NE 425th St
- NE 430th St
- NE 435th St
- NE 440th St
- NE 445th St
- NE 450th St
- NE 455th St
- NE 460th St
- NE 465th St
- NE 470th St
- NE 475th St
- NE 480th St
- NE 485th St
- NE 490th St
- NE 495th St
- NE 500th St
- NE 505th St
- NE 510th St
- NE 515th St
- NE 520th St
- NE 525th St
- NE 530th St
- NE 535th St
- NE 540th St
- NE 545th St
- NE 550th St
- NE 555th St
- NE 560th St
- NE 565th St
- NE 570th St
- NE 575th St
- NE 580th St
- NE 585th St
- NE 590th St
- NE 595th St
- NE 600th St
- NE 605th St
- NE 610th St
- NE 615th St
- NE 620th St
- NE 625th St
- NE 630th St
- NE 635th St
- NE 640th St
- NE 645th St
- NE 650th St
- NE 655th St
- NE 660th St
- NE 665th St
- NE 670th St
- NE 675th St
- NE 680th St
- NE 685th St
- NE 690th St
- NE 695th St
- NE 700th St
- NE 705th St
- NE 710th St
- NE 715th St
- NE 720th St
- NE 725th St
- NE 730th St
- NE 735th St
- NE 740th St
- NE 745th St
- NE 750th St
- NE 755th St
- NE 760th St
- NE 765th St
- NE 770th St
- NE 775th St
- NE 780th St
- NE 785th St
- NE 790th St
- NE 795th St
- NE 800th St
- NE 805th St
- NE 810th St
- NE 815th St
- NE 820th St
- NE 825th St
- NE 830th St
- NE 835th St
- NE 840th St
- NE 845th St
- NE 850th St
- NE 855th St
- NE 860th St
- NE 865th St
- NE 870th St
- NE 875th St
- NE 880th St
- NE 885th St
- NE 890th St
- NE 895th St
- NE 900th St
- NE 905th St
- NE 910th St
- NE 915th St
- NE 920th St
- NE 925th St
- NE 930th St
- NE 935th St
- NE 940th St
- NE 945th St
- NE 950th St
- NE 955th St
- NE 960th St
- NE 965th St
- NE 970th St
- NE 975th St
- NE 980th St
- NE 985th St
- NE 990th St
- NE 995th St
- NE 1000th St
- NE 1005th St
- NE 1010th St
- NE 1015th St
- NE 1020th St
- NE 1025th St
- NE 1030th St
- NE 1035th St
- NE 1040th St
- NE 1045th St
- NE 1050th St
- NE 1055th St
- NE 1060th St
- NE 1065th St
- NE 1070th St
- NE 1075th St
- NE 1080th St
- NE 1085th St
- NE 1090th St
- NE 1095th St
- NE 1100th St
- NE 1105th St
- NE 1110th St
- NE 1115th St
- NE 1120th St
- NE 1125th St
- NE 1130th St
- NE 1135th St
- NE 1140th St
- NE 1145th St
- NE 1150th St
- NE 1155th St
- NE 1160th St
- NE 1165th St
- NE 1170th St
- NE 1175th St
- NE 1180th St
- NE 1185th St
- NE 1190th St
- NE 1195th St
- NE 1200th St
- NE 1205th St
- NE 1210th St
- NE 1215th St
- NE 1220th St
- NE 1225th St
- NE 1230th St
- NE 1235th St
- NE 1240th St
- NE 1245th St
- NE 1250th St
- NE 1255th St
- NE 1260th St
- NE 1265th St
- NE 1270th St
- NE 1275th St
- NE 1280th St
- NE 1285th St
- NE 1290th St
- NE 1295th St
- NE 1300th St
- NE 1305th St
- NE 1310th St
- NE 1315th St
- NE 1320th St
- NE 1325th St
- NE 1330th St
- NE 1335th St
- NE 1340th St
- NE 1345th St
- NE 1350th St
- NE 1355th St
- NE 1360th St
- NE 1365th St
- NE 1370th St
- NE 1375th St
- NE 1380th St
- NE 1385th

Columbia Lombard Mobility Plan – Public Involvement

CHAPTER 03

PLAN PROCESS & COMMUNITY ENGAGEMENT


During the two year Columbia Lombard planning process, we engaged hundreds of businesses, community members, and organizations all along the corridor. The input we received directly influenced the project recommendations.

Engagement Phase 1 | Spring/Summer 2019

What we heard and how it was used

During this round of engagement, **the most consistent theme we heard was the need to improve safety**. A survey and online map asked respondents to identify issues and needs along the corridor. Many felt that improvements were needed for all travel modes, and specifically to improve predictability among road users. Key themes and recommendations are listed below. This input was used, along with the analysis of existing conditions, to develop the project recommendations.

Online survey responses on what corridor-wide issue is most important to address.



KEY TAKEAWAYS

Some general recommendations that were shared:

- Make it **safer to enter/exit**, improve signals/signs, **lower speeds**, add more enforcement, improve road conditions, improve freight route.
- Add **more pedestrian crossings and lighting**, improve sidewalk condition, and add more frequent transit service with better stops
- Create more dedicated, **safe bicycle facilities** and improve crossings.

Columbia Lombard Mobility Plan - Recommendations

CHAPTER 04

PROJECT RECOMMENDATIONS

In general, the plan recommends the following:

- **Better delineate Columbia Blvd as a freight corridor**, improving travel time reliability while improving access and safety
- **Improve the safety of NE Lombard Street** by better managing speeds, improving walking/biking facilities, and adding crossings without significantly impacting traffic operations.
- **Improve north-south connectivity**, specifically for those walking and biking, to access jobs and recreation opportunities
- **Provide low-stress east-west bicycle routes**
- **Improve travel time predictability**

Columbia Lombard Mobility Plan - Recommendations



GOAL FOR SEGMENT

Reduce the high rate of serious crashes for people driving; provide a safe and predictable pedestrian and bicycle network; and ensure freight can move safely and efficiently.






RECOMMENDED IMPROVEMENTS

To improve safety and visibility, lighting should be added on the north side of the street and a median or rumble strips installed to reduce head-on collisions. Wide intersections, like at Columbia Boulevard and I-5, should be narrowed by adding truck aprons. Improvements are also recommended at the intersections of Columbia and Interstate Avenue, Vancouver Avenue, and Martin Luther King Jr. Boulevard, to improve traffic operations and pedestrian safety. Gaps in the sidewalk network should be filled, and crossings should be added at bus stops when planned service begins. A new, higher, railroad bridge is needed to facilitate over-dimensional freight.

Better predictability is needed for people biking. The intersection of NE Argyle and Columbia should be improved to better route people biking east to planned/existing facilities on NE Argyle and N Denver streets.

Finally, automated enforcement and/or speed reader boards should be added to manage excessive speeds and red-light running, especially during off-peak hours.

SPOT IMPROVEMENTS

-  Improve intersection geometry
-  Add/upgrade signal
-  Resurface roadway
-  Railroad improvement
-  fill sidewalk gaps on one or both sides

SEGMENT-WIDE IMPROVEMENTS

- Use access management to reduce head-on and left-turn collisions
- Add lighting
- Add crossings that coincide with future bus service stop locations
- Manage excessive speeding using automated enforcement and speed reader boards

COLUMBIA BLVD. AT NE ARGYLE ST

Safety at the intersection of N Argyle Street/Way and NE Columbia should be improved by eliminating the eastbound right turn slip lane and using the space to provide a better connection for people biking and walking. This will provide a better connection from the path on N Columbia Boulevard to recommended bicycle facilities on N Argyle Way.



UNION PACIFIC RAILROAD BRIDGE

The current Union Pacific railroad bridge does not have sufficient clearance for over-dimensional (extra-tall) freight trucks. Raising the clearance would likely require a new double track bridge to accommodate a future second main line track. While recommended for freight operations, this would be very expensive and would not prevent normal freight from using Lombard Street. To reduce freight traffic on Lombard, a new connection to the St. John's bridge or US 30/NE St Helens Road that reduces out-of-direction travel for freight should be analyzed further. See also page 72, "Planning for Regional Freight Movement."



MLK AND COLUMBIA

This intersection was recently improved, with the addition of a right-turn lane on the northeast corner. However, additional upgrades are still needed. These include adding automated enforcement to prevent red-light running, improving the bus-stop location and amenities, adjusting the signal timing (potentially adding leading pedestrian intervals), and adding turn pockets on the northwest and southeast corners with truck aprons.



PBOT | AREA + PROJECT PLANNING

Columbia Lombard Mobility Plan - Recommendations

Summary of Recommendations for the Columbia Corridor

- **Improve lighting and safety** through signal upgrades, speed reader boards, and raised medians/rumble strips (where possible)
- **Add signage** approaching/along the corridor to highlight street as freight corridor and improve wayfinding
- **Improve transit access** and amenities (preparing for planned expansion of transit service)
- Make **improvements to Freight District Streets** in the area
- Fill sidewalk gaps
- **Add signal at NE Columbia/NE 11th Ave.**
- Make near-term safety **improvements to NE 33rd Ave/NE Columbia Boulevard**, and plan for more significant future improvements
- **Restripe corridor between NE 60th and NE 80th** to improve freight reliability in advance of future widening
- Further **improve MLK Jr. Boulevard/NE Columbia Boulevard**
- Increase vertical clearance under UP railroad bridge


Columbia Lombard Mobility Plan - Recommendations

Summary of Recommendations for the Lombard Corridor

- **Add ITS upgrades** to Lombard between I-5 and I-205
- Improve lighting
- **Extend ODOT's lane reconfiguration** to Denver Ave.
- Add **additional crossings** for people walking and biking and upgrade existing signals
- **Remove on-street parking** between I-5 and NE MLK Boulevard and widen centerline
- **Improve railroad crossing at NE 11th Ave/Lombard**
- **Improve safety between NE 11th and NE 60th avenues** through restriping, access management, and additional signals.
- **Improve ramps** on/off NE 33rd and NE 42 avenues
- Fill sidewalk gaps
- **Improve safety on NE Killingsworth** by installing median where possible, upgrading signals, and enhancing bike facilities
- **Redesign I-205 ramp**

Columbia Lombard Mobility Plan - Recommendations

Summary of Off-Corridor Recommendations



Columbia Lombard Mobility Plan – Additional Recommendations

LIST OF ADDITIONAL RECOMMENDATIONS

- 1 Manage driveway access and gates on corridor
- 2 Integrate stormwater management in redevelopment
- 3 Improve sidewalk condition and standards
- 4 Reduce noise and other environmental pollution
- 5 Improve over-dimensional freight permit process
- 6 Study highway interchange improvements
- 7 Plan for regional freight movement
- 8 Increase transit service along Columbia Boulevard

PBOT | AREA + PROJECT PLANNING

Columbia Lombard Mobility Plan - Implementation

CHAPTER 06

IMPLEMENTATION AND NEXT STEPS

To better focus work plan and manage expectations, projects separated into three categories: “high-readiness,” “medium readiness,” or “low readiness”


- Projects in **“high-readiness” category** most likely to be implemented first, as they:
 - **Address an identified safety need**
 - **Do not need additional project design or refinement**
 - **Can be implemented quickly**
 - **Have a clearly identified source of funding**
- Medium-readiness category also address an identified safety need, but might need additional development/refinement or need to find a suitable funding source

Columbia Lombard Mobility Plan

COLUMBIA PROJECT IMPLEMENTATION

The map below illustrates the projects in the high- or medium-readiness categories for Columbia Boulevard. A full list of projects can be found in Appendix F, and more details on each project can be found in the Recommendations chapter.

High-readiness projects



Medium-readiness projects

COLUMBIA LOMBARD PROJECT LIST

Project name	Project location	Project description	Implementation readiness level	Readiness factors	Plan-level cost estimate
			Low, Medium, High		\$ (<\$3 million), \$\$ (\$3-10 million), \$\$\$ (>\$10 million)
Columbia Corridor Projects					
Columbia Blvd Corridor Lighting Improvements	N/NE Columbia Blvd (Argyle - 82nd)	Add infill street lighting along both sides to meet current standards.	High--Ready for funding opportunities	PBOT has experience with these kinds of lighting projects and has contractors to do the work at a typical cost per mile. Recent funding requests indicate a high likelihood that these projects could be implemented in the coming years.	\$
Columbia Blvd Corridor Safety Improvements	N/NE Columbia Blvd (Argyle - 60th)	Reconfigure skewed intersections to reduce turning speeds, upgrade aging traffic signals, install speed reader boards/automated enforcement and add raised medians or rumble strips where feasible.	High--Ready for funding opportunities	Safety analysis and high-level concept work indicate these are generally feasible and beneficial safety improvements, and could be the basis for state or federal safety funding.	\$\$
Columbia Blvd Access to Transit, Segment 1	N/NE Columbia Blvd (Argyle - 21st)	Fill sidewalk gaps and improve maintenance of existing sidewalks on N/NE Columbia Blvd to improve safety and access to transit for proposed bus line along Columbia Blvd. Provide new bus stops and enhanced crossings to support the new service.	Medium--Needs more project development	TriMet has proposed a new bus line along Columbia Blvd by 2025. Will need to work with TriMet to coordinate in the coming years. May need right-of-way acquisition or dedication in some areas to provide minimum standard sidewalk width.	\$\$
Columbia Blvd Access to Transit, Segment 2	NE Columbia Blvd (21st - 47th)	Fill sidewalk gaps and improve maintenance of existing sidewalks on NE Columbia Blvd from 21st to 47th to improve safety and access to transit, with 33rd to 47th being the highest priority due to higher level of transit service. Consolidate bus stop locations and provide enhanced pedestrian crossings at the remaining stops.	Medium--Needs more project development	Scope is relatively straightforward, but no project development to date. Right-of-way is limited, and utilities and topography can present challenges. Crossing treatments and transit stop changes have not been determined. More work is needed to assess cost and right-of-way needs.	\$\$

Next Steps


- **Plan will soon be public for review, comments being received through March 31**
- **PFC can share comments collectively, individually, and/or by sub-committee**
- **Comments will be incorporated, then a revised draft will be shared with City Council for comment, testimony and adoption in April/May**
- **Work already underway on several projects in the area**

NE 47th Ave Roadway Reconstruction (nearly complete)

NE 47th Avenue from north of Columbia Boulevard to south of Cornfoot Road was one of Portland's most deteriorated road segments. The Portland Bureau of Transportation (PBOT) is completely reconstructing the road, adding multiuse paths on both sides of the street for pedestrians and people biking.



Lombard/Columbia Wayfinding Improvements: Upcoming Street Name Changes (May 2022)



NE Columbia/Cully/Alderwood Project (2022 to 2023)

- Required as part of the PDX Airport Futures Plan to manage traffic flows.
- Will construct new traffic signals at Cully & Columbia and Alderwood & Columbia (replaces existing temporary signal), with side-by-side left turn lanes to manage transitions.
- Will include full modern detection and signal timing system to efficiently manage traffic and prioritize freight movement.
- Includes widening roadway to accommodate future Columbia Blvd widening project in the Transportation System Plan.



NE 42nd Ave Bridge Replacement Project (2022 to 2023)

- Increases vertical clearance over Lombard St (Hwy 30 Bypass), removing major over-dimensional barrier identified in Metro Over-Dimensional Study.
- Removes weight restriction on bridge deck, allowing more freight trucks to use connection between Columbia and Lombard.
- Provides a seismically-safe bridge over a designated Emergency Transportation Route, improving system resiliency.



NE 42nd Ave Bridge Replacement Project (2022 to 2023)

- Increases vertical clearance over Lombard St (Hwy 30 Bypass) to **17'11"**, removing major over-dimensional barrier identified in Metro Over-Dimensional Study.
- Removes weight restriction on bridge deck, allowing more freight trucks to use connection between Columbia and Lombard.
- Provides a seismically-safe bridge over a designated Emergency Transportation Route, improving system resiliency.

Assessing key corridor constraints

City of Portland key corridors constraints and solutions, continued

location ID	constrained location	constraint description	solution(s)
17	P4. NE 42nd Ave Bridge Undercrossing (BR 075/02485)	Bridge clearance height is 15'10", the lowest along the US 30 Corridor, limiting 13 percent of the over-height moves in the region.	NE 42nd/47th Ave Bridge & Corridor Improvements (TSP 40007): Replace the weight-restricted NE 42nd Ave Bridge (#075) over NE Portland Hwy and the adjacent railway, and add pedestrian and bicycle facilities to the bridge and the roadway from Killingsworth to Columbia. This project will remove the weight restriction, maintain vertical clearance for over-dimensional freight, and provide pedestrian and bicycle facilities.


Over-Dimensional Freight Movement Pattern Changes

- Currently, all over-height vehicles traveling east-west on Hwy 30 Bypass must detour to NE Columbia Blvd via NE Lombard Place, and then back to Hwy 30 Bypass via NE Columbia Parkway, to avoid the low-height 42nd Ave Bridge.




Over-Dimensional Freight Movement Pattern Changes

- After upcoming replacement of 42nd Ave Bridge, over-height loads will be able to stay on Hwy 30 Bypass rather than detouring to Columbia Blvd over an at-grade railroad crossing.
- This will allow us to close NE Lombard Place just east of skewed railroad crossing and improve NE 11th Ave to be the main connection over the Kenton Line Railroad, significantly improving traffic, freight, and railroad safety and operations.



NE 42nd Ave Bridge Replacement Project

- Provides wider travel lanes and fully separated pedestrian and bicycle facilities on the bridge deck and approaches.



Bridge

NE 42nd Ave Bridge Replacement Project

- Provides space for a separated bike lane space on Lombard St underneath, rather than current bike lane “drop” that requires bikes to merge into the high-speed travel lane.




11th / Lombard / Columbia

Railroad Crossing and Roadway Improvement Project (currently under development)



11th / Lombard / Columbia

Railroad Crossing and Roadway Improvement Project



11th / Lombard / Columbia

Railroad Crossing and Roadway Improvement Project



11th / Lombard / Columbia

Railroad Crossing and Roadway Improvement Project



11th / Lombard / Columbia

Railroad Crossing and Roadway Improvement Project

- All-way Stop control was added in 2017 through a Railroad Crossing Order as an *interim* safety measure until a better solution could be developed.

BEFORE THE OREGON DEPARTMENT OF TRANSPORTATION

RX 1846

In the Matter of Altering the Highway-Rail Grade)
Crossing NE 11th Avenue at NE Lombard Place on)
UNION PACIFIC RAILROAD COMPANY (UPRR), a)
Delaware Corporation, PORTLAND SUBDIVISION,)
via KENTON LINE, in Portland, Multnomah County,)
Oregon.

INTERIM ORDER

Over the last 10 years the crossing has experienced a number of near misses. The City of Portland has developed an interim solution until such time a more permanent solution is developed. Part of the City's interim solution is to install one new STOP (R1-1) sign for the westbound traffic on NE Lombard Place. The two existing STOP signs will remain in service. All three STOP signs will receive an ALL WAY STOP (R1-3P) plaque mounted below each sign as depicted in the Appendix to this Interim Order.

11th / Lombard / Columbia

Railroad Crossing and Roadway Improvement Project



11th / Lombard / Columbia

Railroad Crossing and Roadway Improvement Project



11th / Lombard / Columbia

Railroad Crossing and Roadway Improvement Project



11th / Lombard / Columbia


Railroad Crossing and Roadway Improvement Project



11th / Lombard / Columbia

Railroad Crossing and Roadway Improvement Project

- PBOT has worked with Kittelson, Associates to develop project to roughly 15% concept design level, to inform decisions on how to proceed with project.




11th / Lombard / Columbia

Railroad Crossing and Roadway Improvement Project

NE 11th/Lombard/Columbia Triangle Area Conceptual Design

Preliminary Design Subject to Change
Date: February 03, 2021



Lombard Street/11th Avenue Design Concept

11th / Lombard / Columbia

Railroad Crossing and Roadway Improvement Project

NE 11th/Lombard/Columbia Triangle Area Conceptual Design

Preliminary Design Subject to Change
Date: February 03, 2021

Vehicle Turning Settings

Design Vehicle: WB-67
Vehicle Speed: 5 mph
Min. Turning Radius: 41'
Turn from stop: Off
Vehicle Envelope
Front Tire Track
Rear Tire Track



Tractor Width	: 8'0"	Lock to Lock Time	: 1.5"
Trailer Width	: 8'0"	Steering Angle	: 25.4°
Tractor Track	: 8'0"	Articulating Angle	: 75.0°
Trailer Track	: 8'0"		

Pavement reconstruction with curbs and multi-use paths on both sides

4.50' Planter Strip
12.50' Shared Path

Can be designed to accommodate a Quiet Zone

Closure of Lombard Place and removal of stop signs supported by Portland Fire Bureau and ODOT Rail as a solution to safety concerns

Lombard Place becomes local access road serving adjacent properties from east

Standard slip lane design

Full signal upgrade, with new railroad interconnect

25.00' Min. From RR CL




Over-Dimensional Freight Movement Pattern Changes

- Currently, all over-height vehicles traveling east-west on Hwy 30 Bypass must detour to NE Columbia Blvd via NE Lombard Place, and then back to Hwy 30 Bypass via NE Columbia Parkway, to avoid the low-height 42nd Ave Bridge.



Over-Dimensional Freight Movement Pattern Changes

- After upcoming replacement of 42nd Ave Bridge, over-height loads will be able to stay on Hwy 30 Bypass rather than detouring to Columbia Blvd over an at-grade railroad crossing.
- This will allow us to close NE Lombard Place just east of skewed railroad crossing and improve NE 11th Ave to be the main connection over the Kenton Line Railroad, significantly improving traffic, freight, and railroad safety and operations.




11th / Lombard / Columbia

Railroad Crossing and Roadway Improvement Project

NE 11th/Lombard/Columbia Triangle Area Conceptual Design

Preliminary Design Subject to Change
Date: February 03, 2021




11th / Lombard / Columbia

Railroad Crossing and Roadway Improvement Project

NE 11th/Lombard/Columbia Triangle Area Conceptual Design

Preliminary Design Subject to Change
Date: February 03, 2016




11th / Lombard / Columbia

Railroad Crossing and Roadway Improvement Project

NE 11th/Lombard/Columbia Triangle Area Conceptual Design

Preliminary Design Subject to Change
Date: February 03, 2021



11th / Lombard / Columbia

Railroad Crossing and Roadway Improvement Project

- ODOT Rail has expressed interest in providing STIP funding for the railroad and signal elements of the project if PBOT agrees to bring the project to 30% design (including railroad diagnostic) and deliver the project.
- Potential to leverage BES stormwater funding and Local Improvement District to pay for street improvements on 11th Ave and surrounding area.
- May need additional funding depending on size of ODOT Rail, BES, and LID funding compared to total project cost.
- In near-term, we need to identify funding to advance from 15% to 30% design, including railroad diagnostic with UP, to ready project for ODOT Rail funding agreement and other leverage opportunities.

Questions?

Bryan Poole: bryan.poole@portlandoregon.gov

Zef Wagner: zef.wagner@portlandoregon.gov